

Republic of thePhilippines PARTIDO DEVELOPMENT ADMINISTRATION Created Under R.A. 7820

Tigaon, Camarines Sur

20	
, 20	20

PRICE QUOTATION

ITEM #		PARTICULARS			UNIT COST	TOTAL COST	
1	CONSTRUCTION OF NEW 5KW DZRP TOWER STATION			lot			
	Scop	pe of Work:					
	B. C. D. E. F. G. Note: 1.	Construction of 100 feet monopole guyed tower including all accessories, hot dip galvanize. Uses A325 nuts and bolts, including grounding system, tower electrical and painting. Installation of heliax cable 7/8 inch with connector for 5KW power output only Installation of 4 Bay Broadband antenna with harness and power divider Dismantling/clearing of existing Trilon Tower Repairs of base foundation and four (4) deadman Installation of adapter 7/8 to 1+5/8 flange Supervision, installation and commissioning. Antenna must be compatible with existing transmitter and other equipment in current use. Monopole tones must be custom built. Heliax cable should be RFS.					
Address: Telephone No.: Contact Person:			_				
Canvas			_				
Sir/Mac	dam:						

PDA-F-PROC/PQ-01 Rev. No. 0 September 1, 2015