



\_\_\_\_\_, 20\_\_\_\_

## PRICE QUOTATION

Sir/Madam:

Please quote your prices of the following articles which this office desire to purchase for use in **installation of 3 phase ATS (Auto Transfer Switch) panel in Garchitorena Water Treatment Plant.**

| ITEM # | ITEM DESCRIPTION   | QTY. | UNIT   | UNIT COST | TOTAL COST |
|--------|--|------|--------|-----------|------------|
|        | Supply of labor, materials, tools & equipment for installation of 3 Phase ATS (Auto Transfer Switch) panel in Garchitorena Water Treatment Plant | 1    | Lot    |           |            |
|        | <b>Parts:</b>  |      |        |           |            |
|        | ATS Panel w/ enclosure wired in nema II STD.   | 1    | Set    |           |            |
|        | Main contactor, 3 pole, 440 VAC w/ coil  | 2    | Pcs    |           |            |
|        | Mechanical interlock   | 2    | Set    |           |            |
|        | Busbar   | 1    | Lot    |           |            |
|        | Din rail   | 3    | Pcs    |           |            |
|        | Digital voltage Monitor (Line to line)   | 1    | Pcs    |           |            |
|        | Under/over voltage controller  | 1    | Pc     |           |            |
|        | On delay timer w/ base   | 3    | Set    |           |            |
|        | Off delay timer w/ base  | 2    | Set    |           |            |
|        | Power relay w/ base  | 2    | Set    |           |            |
|        | 3 phase digital meter  | 1    | Pc     |           |            |
|        | Voltmeter selector switch  | 1    | Pc     |           |            |
|        | Miniature Circuit breaker, 3 pole, 10 amps   | 2    | Pcs    |           |            |
|        | Miniature Circuit breaker, 2 pole, 10 amps   | 2    | Pcs    |           |            |
|        | 3 ph. Stepdown transformer, 440/220 volt   | 1    | Pc     |           |            |
|        | Current transformer, 180/5   | 3    | Pcs    |           |            |
|        | Stranded cable wire, 125mm/ wiring harness   | 80   | Meters |           |            |
|        | Electrical consumables   | 1    | Lot    |           |            |
|        | <b>Labor:</b>  |      |        |           |            |
|        | 1. Fabrication/assy. Of ATS control panel  |      |        |           |            |
|        | 2. Installation of electrical controls & wiring connection<br>Incl. line to line voltage protection  |      |        |           |            |
|        | 3. Elec. Termination at ATS & 3.6 KV/440 VAC high<br>Voltage transformer   |      |        |           |            |
|        | 4. Testing & commissioning of ATS with genset<br>CASURECO 3 phase power supply   |      |        |           |            |

Dealer: \_\_\_\_\_  
TIN: VAT#: \_\_\_\_\_ NON-VAT#: \_\_\_\_\_  
Address: \_\_\_\_\_  
Telephone No.: \_\_\_\_\_  
Contact Person: \_\_\_\_\_  
Canvasser: \_\_\_\_\_

Sir/Madam:

I have the honor to offer my prices for each of the above articles as indicated after each item hereon.

Very truly yours